



Members of the Board

Shannah Tharp-Gilliam, Ph.D.
Chair Person

Emily Kinkad

Sylvia Wilson

Harry Readshaw

Darrin Kelly

Theresa Kail-Smith

Patrick J. Catena

Arietta Scott Williams
Executive Director

Douglas A. Jackson, P.E.
*Director
Operations & Maintenance*

Michelle M. Buys, P.E.
*Director
Environmental Compliance*

Kimberly N. Kennedy, P.E.
*Director
Engineering & Construction*

Karen Fantoni, CPA, CGMA
*Director
Finance*

Michael Lichte, P.E.
*Director
Regional Conveyance*

Jeanne K. Clark
*Director
Governmental Affairs*

Julie Motley-Williams
*Director
Administration*

Erica LaMar Motley
*Director
Scholastic Programs*

JUNE 16, 2025

CONTRACT No. 1800

WET WEATHER PUMP STATION

ADDENDUM No. 2

All bidders bidding **Contract No. 1800** shall read and take note of this **Addendum No. 2**. The Procurement Documents for **Contract No. 1800 WET WEATHER PUMP STATION** are hereby revised and/or clarified as stated below.

Acknowledgement of Contract No. 1800 Addendum No. 2

The Acknowledgement attached to **Addendum No. 2** is to be signed and returned immediately via email at contract.clerks@alcosan.org and acknowledged with Bidder's Proposal.

Kimberly Kennedy, P.E.

Director – Engineering and Construction

ACKNOWLEDGEMENT OF
CONTRACT NO. 1800 G, E, H, P – WET WEATHER PUMP STATION

ADDENDUM NUMBER 2

FIRM NAME: _____

SIGNATURE: _____

TITLE: _____

DATE: _____

June 16, 2025

CONTRACT NO. 1800

WET WEATHER PUMP STATION

ADDENDUM NO. 2

ADDENDUM No. 2

ALLEGHENY COUNTY SANITARY AUTHORITY

PITTSBURGH, PENNSYLVANIA

CONTRACT NO. 1800

WET WEATHER PUMP STATION PROJECT

JUNE 16, 2025

BID OPENING DATE

WEDNESDAY,

AUGUST 19, 2025

11:00 A.M.

This Addendum No. 2 consists of 82 pages and the following attachments:

Attachment A – Pre-Bid Meeting Minutes June 11, 2025 including Presentation (61 pages)

Attachment B – Pre-Bid Meeting Attendance Sheet – 8 ½” x 11” (6 pages)

Attachment C – Addendum No. 2 Drawings – 22” x 34” (5 pages)

ATTENTION BIDDERS

The following additions to and modifications of the Contract Documents will be included in and become part of the Contract for the Allegheny County Sanitary Authority (ALCOSAN) Wet Weather Pump Station. Bidders are instructed to take the following into account in rendering any Bid for this work

The Bidder is responsible for verifying that he/she has received and reviewed all of the pages of the Contract Documents as well as all of the pages and attachments of all addenda. The Bidder shall verify all pages with the table of contents in the Contract Documents and the first page of all Addenda. Receipt of this Addendum No. 2 must be noted on the Bid Form. These items modify the portions of the documents specifically noted; all other provisions of the Contract Documents shall remain in effect

1. PRE-BID MEETING

- 1.1 A Pre-Bid Meeting was held at ALCOSAN at 10:30 a.m., Prevailing Time, on June 11, 2025, in the auditorium of the O&M Building, located at 3300 Preble Avenue, Pittsburgh, PA 15233. Meeting minutes and the attendance sheet are attached (Attachments A and B) to this Addendum No. 2. A site visit to observe the project area and core shed followed the meeting.

2. CHANGES TO THE SPECIFICATIONS

- 2.1 In Specification Section 41 22 13.13 “Radial Bridge Cranes and Hoists”, **ADD** the following after Paragraph 2.07 A 1:

“2. The crane manufacturer shall provide a custom detachable spreader bar for the wet weather pump motors (PWW001-430MO, PWW002-430MO, PWW003-430MO, PWW004-430MO, PWW005-430MO, PWW006-430MO).”

- 2.2 In Specification Section 41 22 13.13 “Radial Bridge Cranes and Hoists”, **ADD** the following after Paragraph 2.07 B 1:

“2. The crane manufacturer shall coordinate with the motor manufacturer to determine the appropriate motor pick-points, center-of-gravity, weight, removal clearance, and other design criteria as required for design of the spreader bar.”

3. CHANGES TO THE DRAWINGS

- 3.1 On Sheet 000-C-23, **ADD** trees at new locations. **REPLACE** Sheet 000-C-23 with Sheet 000-C-23 Rev. 01, refer to Attachment C.
- 3.2 On Sheet 430-M-03, **UPDATE** orientation of motor terminal enclosures. **REPLACE** Sheet 430-M-03 with Sheet 430-M-03 Rev. 01, refer to Attachment C.
- 3.3 On Sheet 430-ET-03, **UPDATE** orientation of motor terminal enclosures and power connection. **REPLACE** Sheet 430-ET-03 with Sheet 430-ET-03 Rev. 01, refer to Attachment C.
- 3.4 On Sheet 000-ESP-04, **UPDATE** size of manhole EMH-224. **REPLACE** Sheet 000-ESP-04 with Sheet 000-ESP-04 Rev. 01, Refer to Attachment C.
- 3.5 On Sheet 430-ED-03, **UPDATE** Details 1 and 2. **REPLACE** Sheet 430-ED-03 with Sheet 430-ED-03 Rev. 01, refer to Attachment C.

4. QUESTIONS AND ANSWERS

- Q1:** Since no Manhole or Handhole sizing details have been provided on Drawing 430-ED-03 and Specification Section 33.05 13.16 can dimensional sizes for the pre-cast manholes and handholes that are required to be provided by the 1800-E Contractor be provided?
- A1:** Precast manholes are shown on drawing 000-ESP-04 as 4' and 8' square. Typical Manhole and Handhole details are shown on 430-ED-03. See specification 26 05 33 for manhole and handhole requirements.
- Q2:** Will the 1800-G Contractor be responsible for the survey and site controls for the physical location of the new duct-banks, manholes and handholes?
- A2:** Survey is the responsibility of each Contract for their respective scope of work. Coordination between Contract 1800G and 1800E is required for locating the ductbanks, manholes and handholes - refer to Section 01 11 00 1.01D and 1.02.C.7. The bidder's use of the words "site controls" is not clear. Please rephrase in a subsequent question.
- Q3:** Will the 1800-G Contractor be responsible for the ductbank trench shoring and excavation stabilization for worker access?
- A3:** Refer to Section 01 11 00 Part 1.02.B.3.

Q4: "Will Section 3.79 Section 3.79 Buy American and 3.80 Pennsylvania Steel Procurement Act be applicable to the following engineered products:

- 26 12 16 Dry Type Medium Voltage Transformers
- 26 13 23 Medium Voltage Metal Enclosed Switchgear
- 26 22 00 Low Voltage Transformers
- 26 24 13 Switchboards
- 26 24 16 Panelboards
- 26 24 19 Motor Control Centers
- 26 28 16.16 Enclosed Switches
- 26 29 23 Variable Frequency Motor Controllers
- 26 36 13 Automatic Transfer Switch "

A4: It is the Contractor's responsibility to establish and manage which engineered products may be granted a waiver or exception to regulatory requirements.

Q5: Drawing 430-ED-01 Detail 14001 details the requirement for a typical conduit duct bank entrance at structure. Drawing 430-ED-05 Detail 18 details the requirement for adjustable gland style sleeves for exterior building penetrations below grade. Drawing 430-ED-05 Detail 13 details a flange conduit sealing bushing below grade. Is Detail 14001 on Drawing 430-ED-01 acceptable for the duct bank entrance into Building 430?

A5: Contract 1800G and 1800E need to coordinate for block out for the building wall. Contract 1800E is responsible for ductbank portion, including conduit reinforcement, concrete, waterproofing, sealing of penetration and appurtenances. Contract 1800G is responsible for excavation and backfill and formwork at wall.

Q6: Which Contract, G or E, is responsible for the interior forming and finishing of concrete at the Building 430 duct bank entrance?

A6: Contract 1800G is responsible for forming and finishing for the wall. Contract 1800E is responsible for the ductbanks. See response to Question 5.

END OF ADDENDUM No. 2

ATTACHMENT – A

Pre-Bid Meeting Minutes and Presentation

CONTRACTS 1800 G, E, H, P
Wet Weather Pump Station
PRE-BID MEETING Minutes

WEDNESDAY JUNE 10, 2025 @ 10:30 AM
ALCOSAN O&M BLDG. AUDITORIUM

JOSEPH TRIPODI – ALCOSAN PROJECT MANAGER
DUSTIN COPENHAVER & BETH JOYCE – ALCOSAN PROJECT ENGINEERS
BRIAN DAUGHERTY – CONSTRUCTION MANAGER

INTRODUCTION

- a. Attendees will be sent a copy of the Agenda/Minutes via email noted on the attendee list.
- b. Opening comments from Construction Manager.
- c. Contractors must purchase bid documents from ALCOSAN to submit bids and receive addendum information.
- d. **Mandatory** goal of WBE/MBE participation. (10% to 25% of contract value).
- e. Presentation of Contract Scope by Brown & Caldwell.

BID DOCUMENTS

1. Legal Notice

- a. Bid security 10% of bid price by certified check or bid bond.
- b. All bids are to be submitted to Alcosan Engineering Department clerks (2nd floor of the O&M Building) on or before bid opening date and time. If the bid package is sent to ALCOSAN by land courier (UPS, FedEx, etc.), allow enough time for delivery to the clerks.
- c. Bid opening on **Tuesday August 19, 2025**, at **11:00 AM** prevailing time
- d. Anticipation of award at the, **Thursday September 25, 2025**, ALCOSAN Board meeting.
- e. All questions about contract documents shall be submitted to Brian Daugherty email to Brian.Daugherty@mbakerintl.com in writing. Any questions by phone or in-person are considered informal and without legal or binding effect on the contract or to the Owner.
- f. The last day for questions is Close of Business **Wednesday July 9, 2025**. Responses will be distributed as addenda, as soon as possible, as deemed applicable.

2. Bidding Documents [Article One]

- a. 1800G Bid Form - fill in TOTAL BASE BID on page 1-5. This is the sum of Lump Sum Work (8.2) and Extended Amount for Unit Price Work (8.1) including 2 Alternatives. 1800 E,H,P Bid Form - fill in Lump Sum on page 1-2. All bids submitted with all bid forms complete and signed by authorized representative of the Company. Only the bid forms need to be submitted (Article1, pages 1-1 through 1-30 (1800G) pages 1-1 through 1-24(E,H,P) and Solicitation and Commitment Statement pages 1 of 4 through 4 of 4), not the entire book.
- b. Acknowledge all Addenda received and made part of the Bid Documents page 1-2 (2.18)
- c. Provide contact for your company in the space designated on page 1-8 for receipt of any communications necessary for the bid evaluation.
- d. Bid Bond - Certified check or Bid Bond. (2.21)
- e. MBE/WBE lower-tier subcontractor participation counts towards 10%-25% (2.27)
- f. Project Labor Agreement (2.36) Primes to sign and submit Letter of Assent with bid. Subs sign before working on project.
- g. Use of Model (2.37) – “facilitate sequencing of the work in preparing bid.”

3. Information for Bidders [Article Two]

- a. Submission of Bids (2.06); Sealed Bid to be submitted to ALCOSAN Engineering Department on or before bid opening date and late bids (anything received after 11:00 AM) will be treated as “non-responsive” and returned to the Bidder unopened.
- b. Award Contract Execution and Notice to Proceed (2.09); Intend to award Contract 1800 at September 25th, 2025, Board Meeting. Contract execution typically requires 4-6 weeks to process paperwork (including bonds and certificates of insurance). Anticipate a Notice to Proceed to be issued November 2025.
- c. Bidders to Investigate (2.15); Bidders are required to visit Core Shed and may coordinate additional site visits through the Construction Manager Resident Engineer Brian Daugherty at Brian.Daugherty@mbakerintl.com.
- d. Tax Exemptions (2.20) See Article 3.22 and Exhibit D.
- e. Bid Security / Contract Execution (2.19)
- f. Alterations of Bids and Documents (2.22)
- g. Qualifications and Experience of Bidders (2.26)
- h. MBE & WBE Participation (2.27)
- i. Project Labor Agreement and Letter of Assent (Prime and Subs) (2.36)
- j. Dispute Review Board (2.38)
- k. Escrow Bid Documents (2.39)
- l. Geotechnical Baseline Report (2.40)
- m. Geotechnical Data Report (2.41)

4. Contract Provisions [Article Three]

- a. Project Coordination (3.7 & 3.28)
- b. Retainage; (3.37): 10% to start. Reduced to 5% at 50% completion.
- c. Bonds (3.58); Performance Bond and Labor and Material Payment Bond to be provided prior to the execution of the Contract Agreement by Owner in the amount (100%) of the Contract Sum. Also, Maintenance Bond (100% of Contract sum) is required upon final acceptance of the completed work.
- d. Working hours (3.77); Normally for an 8-hour period between 7:00 AM to 5:00 PM, Monday through Friday. Work performed after hours, during ALCOSAN holidays and weekends shall be coordinated with the Construction manager 48 hours in advance. **(SCC)**
- e. Pennsylvania Prevailing Wage Rates (3.78); Minimum wage rates as set forth by the PA Prevailing Wage Act. (See Article 7 Volume 1 of 3)
- f. Compliance to the Buy American (3.79)
- g. Compliance to the PA Steel Products Procurement Act/Trade Practices Act (3.80/3.81)

5. Supplemental Contract Conditions

- a. Order Of Precedence (3.2)
- b. Additional Definition (3.3)
- c. Coordination (3.7)
- d. Insurance (3.9)
- e. Access To Work (3.24)
- f. Time Of Completion, Milestone Dates (3.29)
- g. Disputes And Claims (3.56) **For Contract 1800 G only**
- h. Warranty (3.59)
- i. Governing Law; Forum (3.70) **For Contract 1800 G only**
- j. Working Hours (3.77)
- k. Escrow Bid Documents (3.83) **For Contract 1800 G only**
- l. Replace Exhibit “A” Insurance in its entirety with the following Exhibit “A-3SC” Insurance.

- m. For Contract 1800 G only, add Exhibit “E” Dispute Review Board Specification after Exhibit “D” Tax Exemption Certificate.
- n. For Contract 1800 G only, add Exhibit “F” Dispute Review Board Agreement after Exhibit “E” Dispute Review Board Specification.

6. Contract Agreement [Article Four]

- a. Contract Milestones: All 1800 Primes are the same, G shown as example

Construction Milestone	Contract Time Calendar Days	Notes
Substantial Completion of Contract 1800 G	1,797 days	From Notice to Proceed
Final Completion of Contract 1800 G	1,917 days	From Notice to Proceed

- b. Liquidated Damages

Construction Milestone	Liquidated Damages / Calendar Day
Substantial Completion of Contract 1800 G	\$7,000/calendar day
Final Completion of Contract 1800 G	\$7,000/calendar day

7. Bonds, Certificates and Statements [Article 5]

- a. Performance Bond (At beginning of contract)
- b. Labor and Material Payment Bond (At beginning of contract)
- c. Contractor’s Certificate of Satisfaction (At completion of contract)
- d. Maintenance Bond (At completion of contract)

8. Project Specifications [Article 6]

- a. Summary of Work 01 11 00 – Summarized by the FDC

9. Prevailing Minimum Wage Determination [Article 7]

10. Contract Drawings

11. Open Discussion / Questions / Site Tour Requests-submit

- Attendees were informed that any questions asked and responses given are to be considered informal. Attendees must submit questions for formal responses through the Addenda process.
- Site Tour was conducted, and the visitation of core shed was available to attendees after tour.

◆◆◆◆ End of Minutes ◆◆◆◆



ALCOSAN Wet Weather Pump Station Prebid Meeting

Brown AND
Caldwell

June 11, 2025

Agenda


- Project Purpose
- Contract Documents and Reference Documents
- Staging and Coordination
- Constraints and Maintenance of Plant Operations
- Scope and Phasing of Work
 - *Utilities*
 - *SOE and Shaft*
 - *Pump Station Overview*
 - *Commissioning, Warranty*
- Bid Form and Schedule

Project Purpose

Increase treatment capacity at the Alcosan Woods Run WWTP

- Construction of a new 120 mgd pump station and connection to a dewatering tunnel (DWT) built under a separate contract

Wet Weather Pump Station Location



Contract Documents and Reference Information

Four Contracts

- **1800G: General**
- **1800E: Electrical**
- **1800H: HVAC**
- **1800P: Plumbing**

Contract Documents and Reference Info

Bidding Documents

- Volume 1 Front End
- Volumes 2 and 3 Technical Specifications
- Volume 4 Geotechnical Data Report
- Volume 5 Geotechnical Baseline Report
- Drawings

Reference Information

- Volume 1 of 1
- Revit Model

- Rock core storage facility


Staging and Coordination

Brown and Caldwell




Site Utilization

- ① Multiple ongoing and future projects affect access
- ② Tracy Street use is limited by phase and duration
- ③ There will be overlap with truck traffic on Tracy Street from Ohio River Tunnel Project west to east



Staging Near Riverwall

- ① Restricted loading in multiple zones
- ② Must provide unrestricted Alcosan access to electrical substation
- ③ No Contractor river access permitted



General

- Limited onsite soil/rock stockpiling
- Groundwater and construction water (unwatering) to be managed, treated, Alcosan Pretreatment requirements apply
- Management of Excavated Soil and Rock, refer to specifications
- Work hour restrictions refer to specifications
- Special limitations on blasting in vicinity of UOIT and coordination with Sherwin Williams (adjacent property owner)



Constraints and Maintenance of Plant Operation (MOP0)

MOP0 is paramount

SECTION 01 52 00 MAINTENANCE OF PLANT OPERATIONS

PART 1 GENERAL

1.01 SUMMARY

- A. The intent of this specification is to have the Contractor schedule and perform the work in a manner such that the Owner can keep the existing treatment plant facilities in continuous dependable operation and in compliance with all regulatory requirements. The Contractor shall adhere to the constraints listed in this section and elsewhere in the Contract Documents.
- B. Some elements of the phases described in this Section may be achieved in parallel, however Contractor shall adhere to the General and Specific Constraints in the section.
- C. Due to the nature of deep shaft WWPS construction, a significant portion of the permanent HVAC and Plumbing work is anticipated to occur later in the project after major portions of the shaft and substructure have been built.
- D. References to Drawings and drawing keynotes in this section are provided for convenience and are not intended to be comprehensive of all work required as part of a particular Phase.

Long-Lead and Critical Submittals

Refer to Section 01 33 00 Submittals

E. Long-Lead and Critical Submittals

1. Submit within 30 days of Notice to Proceed, critical-path related submittals which may include, but not limited to the following:
 - a. Electrical utilities and piping systems related to utility relocation
 - b. Concrete for ductbanks
 - c. Geotechnical monitoring
 - d. Pre-excavation drilling and grouting, vertical rock reinforcement, slurry walls, rock excavation, shaft construction and temporary support of excavation related submittals.
2. Submit within 90 days of Notice to Proceed, long-lead procurement submittals which are expected to include, but not limited to the following:
 - a. Medium voltage switchgear, variable frequency drives and transformers
 - b. Wet Weather Pumps
3. Refer to individual technical specifications for identification of other anticipated long lead or potentially critical submittals.

Section 01 52 00 Excerpt

Some Phases overlap

Contracts 1800H and 1800P

Work later in project

Keynotes describe some
of the phasing

SECTION 01 52 00 MAINTENANCE OF PLANT OPERATIONS

PART 1 GENERAL

1.01 SUMMARY

- A. The intent of this specification is to have the Contractor schedule and perform the work in a manner such that the Owner can keep the existing treatment plant facilities in continuous dependable operation and in compliance with all regulatory requirements. The Contractor shall adhere to the constraints listed in this section and elsewhere in the Contract Documents.
- B. Some elements of the phases described in this Section may be achieved in parallel, however Contractor shall adhere to the General and Specific Constraints in the section.
- C. Due to the nature of deep shaft WWPS construction, a significant portion of the permanent HVAC and Plumbing work is anticipated to occur later in the project after major portions of the shaft and substructure have been built.
- D. References to Drawings and drawing keynotes in this section are provided for convenience and are not intended to be comprehensive of all work required as part of a particular Phase.

Specific Constraints

Constraints Related to Utility Relocation Prior to SOE, Shaft

Early Action – Electrical Infrastructure Report

Brown and Caldwell


Refer to Section 01 52 00 Maintenance of Plant Operations

- N. Specific Constraint No. 1: The Main Pump Station must remain in service at all times.
- O. Specific Constraint No. 2: Existing utilities shall be relocated prior to beginning slurry wall and related support of excavation work.
- P. Specific Constraint No. 3: Demolition of existing 13.8kV and 5kv medium voltage ductbanks may not occur until the new ductbanks are constructed, cabling is terminated, tested and commissioned.
- Q. Specific Constraint No. 4: A maximum of three days is permitted for shutdown and replacement of each 13.8kV circuit. This includes testing, terminating and commissioning of new 13.8kV circuit and demolition of the existing 13.8kV circuit. Provide temporary power at no cost to the Owner if the Contractor elects to de-energize the existing circuit(s) to accomplish the work in the switchgear or manholes. After completion of Electrical Infrastructure Report described in Part 1.05, in the opinion of the Owner if existing conditions are determined to prevent parallel installation of the new cabling such as a lack of available spare conduits or existing ductbanks and new manhole configurations are found to prevent the installation, temporary power shall be provided for under Specific Allowance #13 Unforeseen Utility Removal and Relocation.
- R. Specific Constraint No. 5: Demolition of existing control and fiber ductbanks may not occur until the new ductbanks are constructed, cabling is terminated, tested and commissioned.
- S. Specific Constraint No. 6: Where redundant electrical cabling such as power from switchgear A side and B side or redundant control cabling is replaced or rerouted, the Construction Manager will establish the minimum number of days required between completion of first outage and start of the next. For the purposes of bidding, assume not less than seven continuous calendar days are required after the completion of the first outage and before the second outage may begin.
- T. Specific Constraint No. 7: Natural gas piping tie-ins shall be performed during the non-heating season in August during the Owners planned 1-week incinerator outage.
- U. Specific Constraint No. 8: The East Headworks Influent Conduit shall remain in service at all times except for the outage described below to connect the new WWPS Effluent Conduit.
- V. Within 30 days from Notice to Proceed, develop and submit an Electrical Infrastructure Report as described in Part 1.05.B.


Utilities

Brown and Caldwell






- 1 Temporary support of ductbanks to 410 Building during drain construction
- 2 Effluent water high pressure above and below ductbanks
- 3 WWPS Effluent Conduit, piles and large plant drain below with later tie into WWPS and East Headworks



Early Phases – Deep Piping and Electrical Ductbanks



- Fieldwork and documentation required to confirm MOPO approach to electrical utility relocation

Section 01 52 00 Example – Refeed Building 410


1.06 Phases 1 and 2 - Work Area 410 Bldg Refeed and Fuel Oil Facility Area.

A. General Description

1. Demolition of infrastructure and refeed of electrical from EMH-113 to Building 410 in advance of WWPS construction.
2. Active power exists in overhead cable tray.
3. Coordination required with Duquesne Light to confirm termination of power in Duquesne Light owned manhole.

B. Reference Drawings

1. 000-G-09 Keynotes 1 and 2.
2. 000-EDM-01 Keynote 1 and 000-ESP-04 Keynote 1.
3. 000-CDM-01 and 03.
4. Work to be completed before shutdown
 - a. Develop and submit an Electrical Infrastructure Report as described in Part 1.05.B of this section to document existing conditions.
 - b. Field measurement verifications shall be completed prior to shop drawing preparation and the information obtained from field measurements shall be incorporated into the shop drawings.
 - c. Submittal and approval of shop drawings and delivery of materials associated with the electrical distribution system, piping and manhole systems.
 - d. Temporary support of existing infrastructure and selective demolition for new ductbank.
 - e. Confirm Duquesne Light termination of power in Duquesne Light owned manhole
 - f. Site and utility demolition in the path of the new ductbank.



KEYNOTES:	
1. 430.01.08 AND 07: DEMOLISH THE ABANDONED FUEL OIL PIPING AND CONTAMINANT AREA, AND REFEED BUILDING 410. ACTIVE POWER EXISTS IN OVERHEAD CABLE TRAY. PROVIDE FOR TEMPORARY SUPPORT OF NEW DUCTBANKS DURING SUBSEQUENT CONSTRUCTION OF THE NEW 48" DRAIN. REFER TO SHEETS 000-EDM-01, 000-ESP-01, 000-CDM-01 AND 03.	8. SPECIFIC CONSTRAINT NO. 4: A MAXIMUM OF THREE DAYS IS PERMITTED FOR SHUTDOWN OF EACH 13.8KV CABLE TO TERMINATE, TEST AND COMMISSION.
2. 430.01.08: DEMOLISH SUBSTATION, ASSOCIATED DUCTBANKS AND ABANDONED ASH PIPING WITHIN THE VICINITY OF THE WWPS AND BOE FOOTPRINT. REFER TO SHEETS 000-EDM-01, 000-ESP-01 THROUGH 04 AND 000-CDM-01 AND 03.	9. SPECIFIC CONSTRAINT NO. 5: DEMOLITION OF EXISTING CONTROL AND FIBER DUCTBANKS MAY NOT OCCUR UNTIL THE NEW DUCTBANKS ARE CONSTRUCTED. CABLEING IS TERMINATED, TESTED AND COMMISSIONED.
3. 430.01.08: PROVIDE BYPASS PUMPING, CONSTRUCT DRAIN PIPING AND NEW MANHOLES (SMH-1 THROUGH SMH-2) BETWEEN THE WWPS AND ERF. EXISTING 48" DRAIN DISCHARGES TO THE MAIN PUMP STATION WET WELL. SUPPORT UTILITY CROSSEINGS TO ERF. REFER TO SHEET 000-CDM-02, 000-C-15 AND 000-ESP-01.	10. SPECIFIC CONSTRAINT NO. 6: WHERE REDUNDANT ELECTRICAL CABLEING SUCH AS POWER FROM SWITCHGEAR A SIDE AND B SIDE OR REDUNDANT CONTROL CABLEING IS REPLACED OR REROUTED, THE CONSTRUCTION MANAGER WILL ESTABLISH THE MINIMUM NUMBER OF DAYS REQUIRED BETWEEN THE COMPLETION OF FIRST OUTAGE AND START OF THE NEXT FOR THE PURPOSES OF BIDDING. ASSURE NOT LESS THAN SEVEN CONTINUOUS CALENDAR DAYS ARE REQUIRED AFTER THE COMPLETION OF THE FIRST OUTAGE AND BEFORE THE SECOND OUTAGE MAY BEGIN.
4. 430.01.08: CONSTRUCT NEW ELECTRICAL UTILITIES AND MANHOLES EAST OF WWPS. IN COORDINATION WITH 48" DRAIN PIPING AND SUBSEQUENT PROCESS AND WATER UTILITIES. REFER TO SHEET 000-ESP-01.	11. SPECIFIC CONSTRAINT NO. 7: NATURAL GAS PIPING TIE-INS SHALL BE PERFORMED DURING THE NON-HEATING SEASON IN AUGUST DURING THE OWNERS PLANNED 2-WEEK INCINERATOR OUTAGE.
5. 430.01.10: CONSTRUCT NEW SANITARY DRAIN FROM THE ERF AND BLOWDOWN (SD) NORTH OF THE ERF. ONCE THE NEW 48" DRAIN IS IN SERVICE, CONSTRUCT NEW SD PIPING FROM NEW MANHOLE BL-1 TO SMH-3. REFER TO SHEET 000-C-15.	12. SPECIFIC CONSTRAINT NO. 8: THE EAST HEADWORKS INFLUENT CONDUIT SHALL REMAIN IN SERVICE AT ALL TIMES EXCEPT FOR THE OUTAGE DESCRIBED BELOW. SEE NOTE 17 TO CONNECT TO THE NEW WWPS EFFLUENT CONDUIT.
6. 430.01.11: CONSTRUCT ELECTRICAL UTILITIES AND MANHOLES SOUTH OF THE WWPS. REFER TO SHEET 000-EDM-01 AND 000-ESP-01.	
7. 430.01.12: COORDINATE CONSTRUCTION OF PORTION OF EFFLUENT CONDUIT TO PERMIT THE CONSTRUCTION OF DUCTBANKS ABOVE CONNECTION TO DISCHARGE CHAMBER AND EXISTING EAST HEADWORKS CONDUIT TO A LATER TIE-IN.	
8. 430.01.13: CONSTRUCT ELECTRICAL DUCTBANKS AND MANHOLES NORTH OF THE WWPS. REFER TO SHEETS 000-ESP-01 AND 000-EDM-01 AND ESP-04.	
9. 430.01.14: CONSTRUCT 13.8KV AND CONTROL CABLEING. SEE SHEETS 000-EDM-01 AND ESP-01 THROUGH ESP-04.	
10. 430.01.15: CONSTRUCT EWH SERVICE LOOP WITH BRANCH TO WWPS FOR SUBSEQUENT TIE-IN ONCE WWPS SUBSTRUCTURE IS COMPLETE. REFER TO SHEET 000-C-15.	
11. 430.01.16: CONSTRUCT PCW SERVICE LOOP WITH PCW AND FIRE WATER BRANCH TO WWPS FOR SUBSEQUENT TIE-IN ONCE WWPS SUBSTRUCTURE IS COMPLETE. REFER TO SHEET 000-C-15.	
12. 430.01.17: DUCTBANKS WEST: CONSTRUCT ELECTRICAL DUCTBANKS AND MANHOLES ALONG THE WEST AND NORTH SIDE OF THE WWPS FOOTPRINT. REFER TO SHEET 000-EDM-01 AND 000-ESP-01 THROUGH ESP-04.	
13. 430.01.18: CONSTRUCT NEW SANITARY DRAIN TO APPROXIMATE INTERFERENCE WITH NEW SMH-3 AND SMH-4. TIE IN DEFERRED UNTIL COMPLETION OF SUPERSTRUCTURE. REFER TO SHEET 000-C-015.	
14. 430.01.19: CONSTRUCTION PORTIONS OF REGULATION PIPE IN COORDINATION WITH PARALLEL 48" DRAIN STAGE FOR SUBSEQUENT TIE-IN.	
15. 430.01.20: CONSTRUCT NATURAL GAS PIPING TO WWPS FROM SOUTH OF ERF ONCE STRUCTURE IS COMPLETE. REFER TO SHEET 000-C-15.	
16. 430.01.21: FINAL UTILITY SERVICE CONNECTIONS TO WWPS.	
17. 430.01.22: ISOLATE EAST AND WEST HEADWORKS USING STOP LOGS AT MP. EXTEND DISCHARGE CONDUIT TO CLOSURE. DEWATER CONDUIT, REMOVE EXISTING 120" CAP AND CONSTRUCT CLOSURE.	
18. 430.01.23: DWV CONNECTION: HYDRAULICALLY CONNECT WWPS WET WELL TO DWV AT TUNNEL JUNCTION CHAMBER. REFER TO SHEET 000-GT-02.	
19. 430.01.24: CONSTRUCT NEW STORM DRAIN PIPING FROM SOUTH WEST OF WWPS TO MANHOLE SMH-7. REFER TO SHEET 000-C-15.	

ARLETTA SCOTT WILLIAMS
EXECUTIVE DIRECTOR, ALCOSAN
3300 PREBLE AVE
PITTSBURGH, PA 15233
(412) 766 - 4810
www.alcosan.org

ALLEGHENY COUNTY SANITARY AUTHORITY
WASTEWATER TREATMENT PLANT
WET WEATHER PUMP STATION

000-G-09
MAINTENANCE OF PLANT OPERATIONS

Contract: 1800
CAD File Name: 000G09.dwg
Date: 5/16/2025
Sheet: 9 of 405


Geologic Conditions, UOIT, SOE, Groundwater Cutoff, and Protection of Structures

Geologic Conditions

- **Soil:**
 - Fill: Sand and gravel, clay, silt, cobbles, boulders, and man-made debris such as ash, slag, cinders, bricks, metal, wood, etc.
 - Alluvium: Interbedded sand, gravel, clay, silt. Cobbles and boulders possible.
 - Residuum: Directly over bedrock. Dense to very dense, highly to completely weathered siltstone or sandstone.
- **Rock:**
 - Interbedded sedimentary rock, with near horizontal bedding: sandstone, shale, claystone, coal, and limestone
 - Majority: Very Good, Good, or Fair Rock.
 - Approximate areas of Poor or Very Poor Rock
- **Groundwater:**
 - Baseline condition in GBR.
 - Overburden and rock are highly permeable.
- **Gas Conditions:**
 - Potentially gassy.




Table 7-1: Baseline Ground Conditions

Stratum	Top of Stratum Elevation (ft)
Fill	727 +/- 2
Alluvium	690 +/- 5
Residuum	680 +/- 2
Bedrock	677 +/- 3




UOIT

- Existing UOIT invert shown approximate
- Vertical rock reinforcement as a shield to protect UOIT
- Restrictions in proximity to UOIT:
 - Drill in 1-foot increments and observe cuttings
 - Downhole survey of hole verticality
- Has to be installed prior to excavation of shaft in rock
- Geotechnical instrumentation and monitoring (later slides)




Pre-excitation Grouting

- Primary 1, 2, and 3:
 - All Primary holes required
 - Max spacing on center defined, extending below base slab
 - Reduced pressures for holes adjacent to UOIT
 - If split spacing criteria is exceeded, drilling and grouting of secondary holes is required (*secondary holes not shown*)
 - Verification holes
 - Needs to be completed prior to excavation in rock




Shaft SOE - Soil

- Engineer-designed SOE
- Embedded into rock
- Loading restrictions on adjacent river wall
(see earlier slide)
- Potential presence of boulders within soil – see Pay Item 13 – Special Allowance #2
- Demolishing of slurry wall is subject to restrictions




Shaft Support - Rock

- Rock Excavation:
 - Height limitation for rock excavation
 - Probing and cutoff grouting as excavation is advanced
 - Initial support to be installed in its entirety prior to advancing the excavation
 - Blasting not allowed in areas adjacent to UOIT, as shown on the Contract Drawings
 - Base slab key



Probing and Cut-off Grouting

- Install around shaft perimeter at each level
- Alternate probe hole locations between levels
- Reduced pressures required adjacent to UOIT
- Manage groundwater to construct permanent works



Control of Groundwater and Construction Water - 31 23 19

1. Construction Water, Groundwater, Surface Water and Unwatering
2. Dewatering of near surface excavations below water table; Slurry wall to be made relatively watertight
3. Unwatering of water that collects in the WWPS shaft, TJC and near-surface excavation and open cuts
4. Discharge location and maximum flowrate restrictions identified in 31 23 19
5. Testing and treatment by Contractor is base bid – per Spec 31 23 19 & Appendix, needs to meet Alcosan Pretreatment Requirements.



Ground Water Discharge Permit Application (For on-site construction related to groundwater disposal)

Applicant Information	
Company Name or Permittee:	Date:
Project Name:	
Company Mailing Address:	
Street Address	
City	State ZIP Code
Person to contact regarding ground water discharge:	
Phone:	Email:
Name:	Company:
Ground Water Discharge Location:	
ATTACH DRAWINGS WITH DESCRIPTIONS	
Will there be flexibility in the dewatering system to discharge to the river if it is determined by sampling that it can be discharged directly to the river?	
	YES <input type="checkbox"/> NO <input type="checkbox"/>
If No, why not?	
Location(s) where ground water sample may be taken:	
Ground Water Flow: <input type="checkbox"/> Continuous – Rate ____GPD <input type="checkbox"/> Intermittent – Rate ____GPD	
If Intermittent, time of discharge: ____ AM / PM to ____ AM / PM	
Days per week (Circle day): Mon. Tues. Wed. Thurs. Fri. Sat. Sun.	
Provide a description of the flow ranges expected (Average and Peak), if it will be continuous or intermittent, timeframes, etc.:	

Groundwater and Construction Water, Soil, Rock and Other Encountered Material

1. Testing and treatment by Contractor is base bid
2. Observation of soil and rock testing by Construction Manager, but testing by Contractor
3. Soil, Rock and Other Encountered Material M&P

PART 3 - EXECUTION

3.1 PAY ITEMS

- A. Pay Item 1 – WWPS Construction Lump Sum Work
 1. The lump sum bid price for this work includes work identified in the Contract Documents and as summarized in Section 01 11 00, Summary of Work.
 2. Work associated with unit price and allowance items as identified in this Section will not be paid under this pay item.
 3. Measurement and payment for this item will be a physical percent complete as agreed by the Construction Manager and Contractor per the Contractor's Schedule of Values.
 4. Payment for this pay item will be made at the lump sum bid price, which will include all labor, materials, equipment, tools, testing, fees, and incidentals needed to complete the work specified, except as otherwise itemized in the Schedule of Values.
 5. All mechanical, civil, architectural, and structural improvements performed as part of this project is considered part of this lump sum bid price.
 6. All temporary support of excavation (SOE) systems and rock initial support are considered part of this lump sum bid price.
 7. Temporary Water Control
 - a. All regulatory testing and treatment of all fluid discharged from temporary water control systems as described in Section 31 23 19, to control construction water and groundwater to meet applicable regulatory requirements is considered part of this lump sum bid price.
 - b. Furnishing, delivery, installation, maintenance, operation, monitoring and removal of all temporary water control systems to control groundwater and construction water is considered part of this lump sum bid price.
 - c. Coordination with Construction Manager who may observe the regulatory testing performed by Contractor.
 8. Regulatory Testing – subsurface work
 - a. All sampling, testing and analysis of all excavated materials for compliance with applicable regulatory requirements including but not limited to soil, rock and other encountered material during subsurface work, pile drilling, temporary SOE work, grout hole drilling, probe hole drilling, spoils, handling, hauling and disposal.
 - b. Coordination with Construction Manager who may observe the regulatory testing performed by Contractor.
 9. Excavation, handling, stockpiling, hauling and disposal – Soil and Other Encountered Material
 - a. Beyond the circumference of the outer diameter of the shaft slurry wall and below grade, all excavation, handling, stockpiling, hauling and disposal of soil, rock, spoils and other encountered material during subsurface work is considered part of this lump sum bid price.


ALCOSAN Contract No. 1800

ALCOSAN
Wet Weather Pump Station
MEASUREMENT AND PAYMENT (LUMP SUM AND UNIT PRICES)
01 22 00 - 6


April 2025

Groundwater and Construction Water, Soil, Rock and Other Encountered Material

1. Testing and treatment by Contractor is base bid
2. Observation of soil and rock testing by Construction Manager, but testing by Contractor
3. Soil, Rock and Other Encountered Material M&P

- 
- i. All material shall be assumed to be Residual Waste as described in Section 31 23 00.
 - b. Within the circumference of the outer diameter of the guidewalls, shaft slurry wall and below grade, all excavation, handling, stockpiling, hauling and disposal of soil and other encountered material during subsurface work, is considered part of this lump sum bid price.
 - i. All material above approximate elevation 693 shall be assumed to be Residual Waste as described in Section 31 23 00.
 - ii. All material below approximate elevation 693 to the top of rock interface shown in the GBR shall be assumed to be Clean Fill as described in Section 31 23 00.
 - c. If regulatory compliance testing confirms Residual Waste material in excess of the above assumptions, refer to Pay Item 22 – Additional Residual Waste Soil Disposal for payment.
 10. Excavation, handling, stockpiling, hauling and disposal – Rock and Other Encountered Material
 - a. Within the circumference of the outer diameter of the guidewalls, slurry wall and below including the shaft and the tunnel junction chamber, all excavation, handling, stockpiling hauling and disposal of rock and other encountered material below the soil interface is considered part of this lump sum bid price. Disposal of rock that is not identified as Acid Producing Rock per item b. below is considered part of this lump sum bid price.
 - b. If regulatory compliance testing in accordance with PennDOT Publication 293, Chapter 10 confirms Acid Producing Rock refer to Pay Item 23 – Acid Producing Rock Disposal for payment.

Geotech Monitoring



- Geotechnical Instrumentation

- GMP, SMP, UMP, Tiltmeter, Inclinator, Piezometer, Seismographs, Down-hole seismographs
- Alert and maximum permissible movement levels
- Installed and baseline prior to construction.


Alert and Maximum Levels of Instruments		
Monitor	Alert Level	Maximum Level
Slurry Wall (structure monitoring point)	0.50 in (horizontal) 0.25 in (vertical)	1.00 in (horizontal) 0.50 in (vertical)
Inclinometers	1.00 in (horizontal)	2.00 in (horizontal)
Discharge Piping Floor SOE	1.00 in (horizontal) 0.25 in (vertical)	2.00 in (horizontal) 0.50 in (vertical)
Existing Structures (Energy Recovery Facility, Tower, Main Pump Station)	0.15 in (horizontal) 0.15 in (vertical) 1/500 (angular distortion)	0.25 in (horizontal) 0.25 in (vertical) 1/250 (angular distortion)
Grid Crack Gauges*	0.075 in	0.125 in
Existing River Wall	0.50 in (horizontal) 0.50 in (vertical) 1/500 (angular distortion)	1.00 in (horizontal) 1.00 in (vertical) 1/250 (angular distortion)
Buried Pipelines and Utilities	0.20 in (vertical)	0.30 in (vertical)
Electrical Conduits (newly installed)	0.50 in (vertical)	0.75 in (vertical)
Pavement outside the staging area	0.15 in (horizontal) 0.15 in (vertical)	0.25 in (vertical) 0.25 in (vertical)

* Grid Crack Gauges to be installed by contractor, see Section 02 20 00


Shaft Permanent Construction and TJC interface with ORT Contract

Construction of Shaft – Unique Elements


- Waterproofing membrane system
- Mass concrete placement requirements:
 - Temperature Control Plan
- Durable concrete mix design:
 - Alkali-silica reactivity testing (long-lead)
- True circular forms
- Minimum thicknesses to be maintained
- Construction joint layout:
 - Coordination of reinforcement and waterstops
 - Layout restrictions
- High tensile concrete fill geometry
- Underhung circular crane system embedded supports
 - Field fit
- Contractor-designed aluminum access platforms






Tunnel Junction Chamber – Initial Support



- Tunnel Junction Chamber Initial Support:
 - WWF shotcrete lagging with steel ribs
 - Dowels and spiles
 - Engineer-designed
 - Blasting limitations at Contract interface




Tunnel Junction Chamber Permanent Sections & Details




- Flat roof slab required for TJC hydraulics
- Backfill above roof slab with low density backfill
- Coordination of TJC penetration with waterproofing membrane for shaft liner.

Tunnel Junction Chamber – Interface with ORT



- Two alternatives at the tie-in driven by timing of schedule of WWPS Project and Ohio River Tunnel Project
 - Alternative 1 – ORT work at the interface complete prior to WWPS
 - Alternative 2 – WWPS work at the interface complete prior to ORT
- Contractor-designed Bulkhead
- DWT Transition Section
- Contractor shall bid both alternatives, paid for one


Discharge Piping Floor SOE System



- Shallow SOE system:
 - Contractor-designed
 - Performance criteria in Contract Documents
 - Requires coordination with Engineer-designed slurry wall
 - Slurry wall may not be demolished until shaft permanent liner is installed to underside of Discharge Piping Floor
 - Groundwater Control

Pump Station Overview

Brown and Caldwell




Multiple Levels

- Electrical Room, HVAC Area
 - Entry Level
 - Discharge Piping Level


Superstructure pile supported

- Motor Level
- Wet Weather Pump Floor
- Basement Level – Pump Suction and Emergency Drain Pumps




Pump, Motor and Basement Levels


- (6) 30 mgd pumps/motors
- Suction/discharge piping, valving, and flow meters
- Radial cranes at multiple levels
- Shaft-handling system
- Floor access hatches
- HVAC and plumbing work extends to lower levels




Pump Room and Radial Crane System




Brown and Caldwell



Motor Room and Radial Crane System




Brown and Caldwell




41

Radial Crane with Telescoping Girder



Brown and Caldwell


Pump Room



Motor Room


Discharge Pipe Level

- Discharge piping
- Discharge structure
- Cone Valves
- Access hatches
- Recirculation pipe drop structure




Entry Level ~ El. 730.75

- Discharge pipe/siphon break valving
- (2) Loading docks with cranes
- Floor hatches
- Wet well access room with covered openings
- Restroom/janitor closet
- Masonry wall construction separating process areas



Grade Level

- Odor control carbon scrubber system with vessels outdoors
- Fan Room
- System serves multiple areas




Electrical/HVAC Level

- Electrical Room
- Elevator Control Room
- HVAC Rooftop Units and MAUs within masonry screening walls



Roof Level

- HVAC Rooftop Units and MAUs
- Elevator access
- EPDM roofing system



Facade

View from Northwest




WWPS View from Tracy Street



Brown and Caldwell


WWPS View from River Wall




Brown and Caldwell

WWPS Brick Shapes


- Standard




- Brick Shape 1




- Brick Shape 2




- Brick Shape 3




- Brick Shape 4




- Brick Shape 5



- Brick Shape 6




Brown and Caldwell





Phase 6 – Commissioning and Warranty

WWPS Potential Idle Period

- Refer to Section 43 23 16
- Pumps are installed but idle until tunnel is completed and adit connection made
- Recirculation mode using recirculation pipe only permits startup and operation at low suction head only
- Special Warranty on Wet Weather Pumps
- Pump 'Health Assessment' required
- Testing during actual wet weather events is required once Ohio River Tunnel is commissioned



WWPS – Recirculation Mode for Startup Prior to Adit Connection



Bid Form, Contract Schedule

Bid Form 1800G

Item	Description	Quantity	Unit	Unit Price	Extended Total Amount
01	WWPS CONSTRUCTION LUMP SUM WORK	1	LS		\$
02	DRILLED MICROPILES	9003	VLF		\$
03	STATIC COMPRESSION AND TENSION VERIFICATION PILE LOAD TESTS	2	EA		\$
04	PRE-EXCAVATION GROUT HOLD DRILLING IN SOIL	3,255	LF		\$
05	PRE-EXCAVATION GROUT HOLE DRILLING IN ROCK	10,590	LF		\$
06	PROBE HOLE DRILLING IN ROCK	2,700	LF		\$
07	SHAFT PRE-EXCAVATION GROUTING EXCLUSIVE OF GROUT MATERIALS	600	CREW HOURS		\$
08	CUT-OFF GROUTING EXCLUSIVE OF GROUT MATERIALS	100	CREW HOURS		\$
09	INITIAL SUPPORT SPOT ROCK DOWELS	2050	LF		\$
10	ALTERNATIVE 1 CONNECTION TO ORT CONTRACT DEWATERING TUNNEL	1	LS		\$
11	ALTERNATIVE 2 CONNECTION TO ORT CONTRACT DEWATERING TUNNEL	1	LS		\$
12	SPECIFIC ALLOWANCE #1 – DISPUTE REVIEW BOARD (DRB)	250,000	USD	N/A	\$
13	SPECIFIC ALLOWANCE #2 – STOPPAGE TO SLURRY WALL TRENCH EXCAVATIONS	250,000	USD	N/A	\$
14	SPECIFIC ALLOWANCE #3 – DRILLING THROUGH OBSTRUCTIONS FOR MICROPILE INSTALLATION	50,000	USD	N/A	\$
15	SPECIFIC ALLOWANCE #4 – DISPOSAL OF OTHER CONTAMINATED WASTE	500,000	USD	N/A	\$
16	SPECIFIC ALLOWANCE #5 – NON-COMPLIANT GROUNDWATER DISPOSAL	100,000	USD	N/A	\$
17	SPECIFIC ALLOWANCE #6 – HANDLING AND DISPOSAL OF LEAD-BASED COATINGS AND ASBESTOS-CONTAINING MATERIALS (ACM) (GREATER THAN 1 PERCENT ASBESTOS)	25,000	USD	N/A	\$
18	SPECIFIC ALLOWANCE #7 – EXCAVATION OF "HARD SLAG" REMOVAL	1,000	CY		\$

Item	Description	Quantity	Unit	Unit Price	Extended Total Amount
19	SPECIFIC ALLOWANCE #8 – EXCAVATION AND DEMOLITION OF UNFORESEEN CONCRETE, MASONRY, AND OTHER MANMADE OBSTRUCTIONS	200	CY		\$
20	SPECIFIC ALLOWANCE #9 – CONTINGENT UNCLASSIFIED EXCAVATION	2,000	CY		\$
21	SPECIFIC ALLOWANCE #10 – CONTINGENT PLACEMENT OF BACKFILL MATERIAL	2,400	CY		\$
22	SPECIFIC ALLOWANCE #11 – ADDITIONAL RESIDUAL WASTE SOIL DISPOSAL	14,400	TONS		\$
23	SPECIFIC ALLOWANCE #12 – ACID PRODUCING ROCK DISPOSAL	43,400	TONS		\$
24	SPECIFIC ALLOWANCE #13 – GROUT MATERIALS USED FOR PRE-EXCAVATION GROUTING AND CUT-OFF GROUTING	250,000	USD	N/A	\$
25	SPECIFIC ALLOWANCE #14 – UNFORESEEN UTILITY REMOVAL AND RELOCATION	100,000	USD	N/A	\$
	TOTAL OF EXTENDED ITEM AMOUNTS FOR UNIT PRICE WORK LISTED ABOVE (Sum of Extended Total Amount for 01 thru 25)				\$

Contract No.1800 G

8.2 Base Bid Summary:

TOTAL BASE BID:

_____ Dollars
(Words)

and _____ Cents. \$ _____
(Words) (Figures)

Bid Forms for 1800E, H and P

8. BASE BID.

8.1 Lump Sum Work: Bidder further agrees to accept as full payment for the Lump Sum Work proposed within the Bidding Documents based upon the undersigned's own estimate of quantities and costs and including sales, consumer, use, and other taxes, except as provided below, and overhead and profit, for **CONTRACT NO. 1800 E** the following lump sum of:

Dollars

(Words)

and Cents \$

(Words) (Figures)

8. BASE BID.

8.1 Lump Sum Work: Bidder further agrees to accept as full payment for the Lump Sum Work proposed within the Bidding Documents based upon the undersigned's own estimate of quantities and costs and including sales, consumer, use, and other taxes, except as provided below, and overhead and profit, for **CONTRACT NO. 1800 P** the following lump sum of:

Dollars

(Words)

and Cents \$

(Words) (Figures)

8. BASE BID.

8.1 Lump Sum Work: Bidder further agrees to accept as full payment for the Lump Sum Work proposed within the Bidding Documents based upon the undersigned's own estimate of quantities and costs and including sales, consumer, use, and other taxes, except as provided below, and overhead and profit, for **CONTRACT NO. 1800 H** the following lump sum of:

Dollars

(Words)

and Cents \$

(Words) (Figures)

Questions

ATTACHMENT – B

Pre-Bid Meeting Attendance Sheet

ALLEGHENY COUNTY SANITARY AUTHORITY

Pre-Bid Meeting Attendance

PROJECT: Wet Weather Pump Station	CONTRACT NO. 1800
DATE: Wednesday, June 11, 2025	TIME: 10:30 A.M.

	NAME	AFFILIATION	PHONE	E-MAIL
1	Jeff Argyros	ALCOSAN	(412) 734-6281	jeff.argyros@alcosan.org
2	Matt Gilfillan	ALCOSAN	(412) 734-8361	matthew.gilfillan@alcosan.org
3	Joe Tripodi	ALCOSAN	(412) 734-8709	joseph.tripodi@alcosan.org
4	Tyler Trainor	ALCOSAN	(412) 766-4810 x8232	tyler.trainor@alcosan.org
5	Jim MARQUART	J.F. SHOR Constr. Inc.	(508) 277-1660	Jim.Marquart@JFSNER.COM
6	Matt Over	Schnabel	(925) 222-0313	mover@schabel-eng.com
7	Heather Dolson	BC	(412) 599-217	hdolson@bruncald.com
8	JEFF HITT	BC	(216) 606-1316	j.hitt@bruncald.com
9	Bruce Ball	BC	()	bball@bruncald.com
10	ROD SHOULDERS	J.D.C	(216) 738-9579	rshoulders@jaydee.us
11	James Jundicelli	Jay Dee Contractors	(216) 870-6745	jundicelli@jaydee.us
12	PAUL HARTLEY	SBB USA Construction	(724) 265-4600	phartley@sbbkvausa.com
13	Ryan Wagner	Fay	(724) 265-4600	RWAGNER@JBFAYCO.COM
14	CRAIG HAMILTON	KELLER-NA	(804) 405-3208	Craig.Hamilton@KELLER-NA.com

ALLEGHENY COUNTY SANITARY AUTHORITY

Pre-Bid Meeting Attendance

PROJECT: Wet Weather Pump Station	CONTRACT NO. 1800
DATE: Wednesday, June 11, 2025	TIME: 10:30 A.M.

	NAME	AFFILIATION	PHONE	EMAIL
15	Chris Delewa	Joseph B. Fay	(412) 471-4200 x106	cdelewa@shikunusa.com
16	Charles Zugell	JBB Construction	(412) 665-6112	czugell@shikunusa.com
17	ANDY GRAFT	OSCAR RENDA	(412) 631-1000	Biddingteam@SOUTHANDHOLDS.com
18	SCOTT VARLO	SSM	(412) 965-9264	
19	Hunter Barone	SSM	(412) 892-0805	hbarone@ssmi.biz
20	Mike Fitzgerald	Brann & Caldwell	(724) 759-9380	mfitzgerald@brann-cald.com
21	AL LASH	Clista Electric	(878) 2085096	alash@clistaelectric.com
22	Craig Robash	Wellington Power	(412) 287-3398	crobash@wellingtonpower.com
23	JOSEPH MICHALKA	Wellington Power	(412) 302-2260	jmiculka@wellingtonpower.com
24	DAVID SPANO	BRAYMAN	(412) 585-7326	ESTIMATOR@BRAYMAN.COM
25	Denny March	BRAYMAN	(878) 250-0322	d-march@brayman.com
26	MATT FLEURY	MASCARO	(412) 321-4901	M.FLEURY@MACAROLCONSTRUCTION
27	Dave DeChicchi's	MASCARO	(412) 290-5646	ddechicchi@macarolconstruction.com
28	PAT GRIN	NTE	(724) 344 6971	pgrin@nterests.com

ALLEGHENY COUNTY SANITARY AUTHORITY

Pre-Bid Meeting Attendance

PROJECT: Wet Weather Pump Station	CONTRACT NO. 1800
DATE: Wednesday, June 11, 2025	TIME: 10:30 A.M.

	NAME	AFFILIATION	PHONE	EMAIL
29	John Wise	Nicholson	(412) 389-1604	john.wise@nicholsonconstruction.com
30	William Beck	Nicholson	(412) 720-3829	william.beck@nicholsonconstruction.com
31	Greg Franz	Trumbull Corporation	(412) 292-8312	greg.franz@trumbullcorp.com
32	Harry Hardman	3 Rivers Tunnel Constructors A Joint Venture	(412) 807-2150	hhardman@trumbullcorp.com
33	GREG COSTA	WG TOMKO	(724) 348-2000	gcosta@wgtomko.com
34	DAN PAULOVICH	WAYNE CROUSE, INC	(724) 601-0994	dpaulovich@waynecrouse.com
35	FRED VOGT	WAYNE CROUSE, INC	(412) 398-0271	fvogt@waynecrouse.com
36	Mike Culbertson	Keller	(330) 413-1787	mike.culbertson@keller-usa.com
37	Ken Praytas	National TRENCH SAFETY	(412) 352-2534	ken@nationalpraytas.com
38	David Whitlatch	A&A Consultant	(724) 635-9543	dwhitlatch@aconsultantsinc.com
39	Jen Kilburn	A&A Consultants	(724) 635-9543	jkilburn@aconsultantsinc.com
40	Mac Ross	JF Shea	(814) 404-4778	mac.ross@jfshea.com
41	Mike Ladkey	MOSITES CONST.	(412) 923-2255	mikel@mosites.com
42	Jacob Luarte	Obayashi	(650) 619-6382	Jacob.Luarte@obayashi-usa.com
43	Dan Kelly	Multivista	(412) 295-4292	d.kelly@multivista.com

ALLEGHENY COUNTY SANITARY AUTHORITY

Pre-Bid Meeting Attendance

PROJECT: Wet Weather Pump Station	CONTRACT NO. 1800
DATE: Wednesday, June 11, 2025	TIME: 10:30 A.M.

	NAME	AFFILIATION	PHONE	EMAIL
44	Hayden Nussel	Sargent Electric	(412) 523-1788	hnussel@sargentelectric.com
45	ERIC MORA	SARGENT ELECTRIC	(412) 354-7870	emora@sargentelectric.com
46	SAAWNA MUNN	AECON GROUP	()	smunn@aecon.com
47	COREY HALL	"	()	chall@aecon.com
48	GIL BERRY	GIL BERRY & ASSOCIATES DBE	(412) 720-1448	GILBERRY60@YMAIL.COM
49	LORENE BERRY	GIL BERRY & ASSOCIATES DBE	(412) 996-0274	LORENE.BERRY@GILBERRYASSOCIATES.COM
50	Ronie Guzman	Obayashi corp.	(954) 504 9362	ronie.guzman@obayashi-usa.com
51	STUART SULLIVAN	"	(512) 470-0237	STUART.SULLIVAN@OBAYASHI-USA.COM
52	Dmka Chappel	AIG	(412) 722-0065 x242	DCHAPPEL@AIGCONTROLS.COM
53	Steve McManis	Mele & Mele & Sons	(412) 606 3863	smcmannis@meleinc.com
54	RALPH J. PAGONE	GOETTLE	(412) 298 9139	rpagone@gottle.com
55	Mike Roarke	PJ Dick	(412) 977-5990	mike.roarke@pjchick.com
56	John Reinert	Thoroughbred	(784) 816 6278	jreinert@thetcg-electric.com
57	JOSEPH RESTELLI	"	(412) 789-6415	JRESTELLI@THETCGELECTRIC.COM
58	BRAD ZOOK	MICHAEL BAKER INTL	(717) 320 4682	bradley.zook@mbakerintl.com

ALLEGHENY COUNTY SANITARY AUTHORITY

Pre-Bid Meeting Attendance

PROJECT: Wet Weather Pump Station	CONTRACT NO. 1800
DATE: Wednesday, June 11, 2025	TIME: 10:30 A.M.

	NAME	AFFILIATION	PHONE	EMAIL
59	FRANK ZOTTOLA	INDEPENDENCE EXCAVATING	(412) 728-6199	fzottola@indexc.com
60	GARY GUY	Guy's Mechanical Systems	(724) 813-4390	gary@guysmech.com
61	RYAN VAZ	PJ DICK	(724) 384 4600	ryanguy@pidick.com
62	Ben Jacobs	Independence Excavating	(412) 804-8170	bjacobs@indexc.com
63	Beth Joyce	ALCOSAN	(412) 734 8719	beth.joyce@alcosan.org
64	Joe Felix	Xylem	(412) 266 0813	joseph.felix@xylem.com
65	Scott DeBacco	Xylem	(330) 301 9509	Scott.debacco@xylem.com
66	Jared Cardenas	Xylem	(412) 334 0464	Jared.Cardenas@xylem.com
67	Ryan Novelli	Independent Enterprises	(412) 715-9733	RNovelli@ieionet.co
68	Scott Pilsrud	RED SWIRL GROUP	(724) 325-1215	S.PILSRUD@REDSWIRLGROUP.COM
69	Lorenzo Scull	Mosites	(412) 287-5310	lscull@mosites.com
70			()	
71			()	
72			()	

Today's Date: 06/11/2025

Allegheny County Sanitary Authority
Contract 1800 - Wet Weather Pump Station

PRE-BID MEETING SIGN-IN - CORE SHED VISIT

Name	Company	Email	Phone Number
------	---------	-------	--------------

1. STUART SUMNER	OSBY/ATI	STUART.SUMNER@OSBYATI-USA.COM	
------------------	----------	-------------------------------	--

2. COREY HALL	AECOM	CHALL@AECOM.COM	
---------------	-------	-----------------	--

3. SHAWNA MUNN	AECOM	SMUNN@AECOM.COM	
----------------	-------	-----------------	--

4. Chris Deklewa	Joseph B. Foy	cdekleva@shibunusa.com	
------------------	---------------	------------------------	--

5.			
----	--	--	--

6.			
----	--	--	--

7.			
----	--	--	--

8.			
----	--	--	--

9.			
----	--	--	--

10.			
-----	--	--	--

11.			
-----	--	--	--

12.			
-----	--	--	--

13.			
-----	--	--	--

14.			
-----	--	--	--

15.			
-----	--	--	--

16.			
-----	--	--	--

17.			
-----	--	--	--



18.			
-----	--	--	--

19.			
-----	--	--	--


ATTACHMENT – C

Addendum No. 2 Drawings

SUMMARY OF TREES TO BE REMOVED			
BOTANICAL NAME	COMMON NAME	DIAMETER (INCHES)	SUMMED DIAMETER OF TREES (INCHES)
GINKGO BILOBA	GINKO	12	57
GINKGO BILOBA	GINKO	15	
GINKGO BILOBA	GINKO	18	
QUERCUS RUBA	RED OAK	12	
SUMMARY OF TREES TO BE PLANTED			
BOTANICAL NAME	COMMON NAME	DIAMETER (INCHES)	SUMMED DIAMETER OF TREES (INCHES)
15 CORNUS MAS 'GOLDEN GLORY'	15 CORNELIAN CHERRY DOGWOOD	3-5	60




1 TREE PLACEMENT AROUND OPERATION AND MAINTENANCE BUILDING
SCALE: 1" = 50'-0"




2 TREE PLACEMENT ON THE NORTH END
SCALE: 1" = 30'-0"

LEGEND

- ASPHALT PAVEMENT
- CONCRETE
- SEEDING/LANDSCAPING
- GRAVEL PAVEMENT




KEYPLAN



Designed by:	REVISION			
	REV No.	DATE	DESCRIPTION	APPV
L. SPRANKLE	0	5/16/25	ISSUED FOR BID	CC
Drawn by:	1	6/12/25	Add. 2 - Add Additional Trees to North End	CC
L. SPRANKLE				
Checked by:				
C. CASADEI				



Signer: Name: Corrado M. Casadei
Signing Reason: I approved this document.
Signing Time: 2025-06-11 15:26:17 (EDT)



ARLETTA SCOTT WILLIAMS
EXECUTIVE DIRECTOR, ALCOSAN



3300 PREBLE AVE.
PITTSBURGH, PA 15233
(412) 766 - 4810

www.alcosan.org

ALLEGHENY COUNTY SANITARY AUTHORITY
WASTEWATER TREATMENT PLANT
WET WEATHER PUMP STATION

000-C-23
PAVING AND LANDSCAPING PLAN

Contract:	1800
CAD File Name:	000-C-23.dwg
Date:	5/16/2025
Sheet:	36 of 405




MOTOR FLOOR PLAN

- GENERAL NOTES:**
- SEE DETAIL 1/430-M-26 FOR WASHDOWN AND SEAL WATER SYSTEM ISOMETRIC.
- KEYNOTES:**
- VERTICAL NON-CLOG EXTENDED SHAFT WET WEATHER PUMP MOTOR, TYP.
 - MAGNETIC FLOW METER, TYP.
 - TELESCOPING RADIAL BRIDGE CRANE.
 - CONTRACTOR SHALL PROVIDE AND ASSEMBLE ONE DIVERSE SUPPLY, INC. STAINLESS STEEL SINGLE ENTRY MOBILE WORK PLATFORM WITH RAILS MODEL NUMBER DS-SEP6-3648, OR APPROVED EQUAL.
 - INTEGRAL PUMP SHAFT HANDLING SYSTEM INTEGRATED INTO THE MOTOR BASE, TYP.
 - UTILITY STATION. SEE DETAIL D31001/430-MD-07. PROVIDE EACH HOSE RACK WITH A 50 FOOT UTILITY HOSE.
 - TYPE F PIPE PENETRATION. SEE DETAIL 3/430-MD-03.
 - 90-DEGREE BEND UP.
 - DIP-6"-RSW-FE.
 - DIP-16"-RSW-FE.
 - SSP-2"-SLW-PGRV
 - 90 DEGREE BEND DOWN.
 - CBP-30"-RSW-FE
 - FLOOR DRAIN.
 - TEE DOWN.
 - TRENCH DRAIN, TYP. REFERENCE STRUCTURAL DRAWINGS FOR DETAILS.
 - MOTOR TERMINAL ENCLOSURE SHALL HAVE REMOVABLE PANEL. HINGED ACCESS DOORS ARE NOT ALLOWED. MOTOR FLANGE BOLT PATTERN ON PW002-430MO AND PW005-430MO SHALL BE ROTATED 15 DEG FOR CLEARANCE FROM DISCHARGE PIPE.



Plot Date: 6/10/2025 8:47:16 AM Path: BIM 360 // 170064 - ALCOSAN Wet Weather PS/170064-M-430V21.rvt



Designed by: A.JUERGENS	REVISION				Signer Name: Andrew Juergens Signing Reason: I approved this document. Signing Time: 2025-06-11 13:53:20(EDT)			ARLETTA SCOTT WILLIAMS EXECUTIVE DIRECTOR, ALCOSAN 3300 PREBLE AVE. PITTSBURGH, PA 15233 (412) 766 - 4810 www.alcosan.org	ALLEGHENY COUNTY SANITARY AUTHORITY WASTEWATER TREATMENT PLANT WET WEATHER PUMP STATION 430-M-03 MOTOR FLOOR PLAN	Contract: 1800	
Drawn by: R.PAVLISICH	REV No. 0	DATE 5/16/25	DESCRIPTION ISSUED FOR BID							APPV AJ	CAD File Name:
Checked by: C.MICHALOS	1	6/12/25	ADD. 2 - ROTATE MOTOR ENCLOSURE							AJ	Date: 5/16/2025
											Sheet: 221 of 406



- KEYNOTES:**
1. INSTALL DUCTBANK SECTION AND NEW CABLING TO BUILDING 410 IN ACCORDANCE WITH SECTION 01 52 00-01.06.
 2. INSTALL MANHOLES EMH-223, EMH-224, EMH-216, EMH-217, EMH-219, EMH-220, AND ASSOCIATED DUCTBANK SECTIONS BETWEEN THE MANHOLES ON THE EAST SIDE OF THE CONSTRUCTION AREA IN ACCORDANCE WITH SECTION 01 52 00-1.09.
 3. INSTALL DUCTBANK SECTIONS BETWEEN EMH-004 AND EMH-223, EMH-018 AND EMH-219, EMH-044 AND EMH-216, EMH-027 AND EMH-223 ON THE SOUTH SIDE OF THE CONSTRUCTION AREA IN ACCORDANCE WITH SECTION 01 52 00-1.11.
 4. INSTALL MANHOLES EMH-218, EMH-221, EMH-222, EMH-225, AND ASSOCIATED DUCTBANK SECTIONS BETWEEN; EMH-224 AND EMH-225, EMH-220 AND EMH-221, EMH-217 AND EMH-218, EMH-218 AND EMH-222, EMH-218 AND EM-1, EMH-221 AND EMH-106A/B, EMH-222 AND EMH-046, EMH-225 AND EMH-050, AND EMH-225 AND EMH-031. IN ACCORDANCE WITH SECTION 01 52 00-1.13.
 5. INSTALL DUCTBANK SECTIONS BETWEEN EMH-225 AND EMH-031, EMH-225 AND EMH-050, EMH-218 AND EMH-106A/B, EMH-222 AND EMH-046 ON THE NORTH SIDE OF THE CONSTRUCTION AREA IN ACCORDANCE WITH SECTION 01 52 00-1.13.
 6. AFTER THE WET WEATHER PUMP STATION SHAFT AND BUILDING FOUNDATIONS ARE COMPLETED, INSTALL MANHOLE EMH-226 AND ASSOCIATED DUCTBANK SECTION BETWEEN EMH-027 AND EMH-226 ON THE WEST SIDE OF THE CONSTRUCTION AREA IN ACCORDANCE WITH SECTION 01 52 00-1.17.
 7. DUCTBANK SECTION 7 TO BE INSTALLED UNDER SECTION 6.
 8. TEMPORARY CONSTRUCTION POWER SHALL BE SUPPLIED FROM MCC022-410. BUCKET (7A) 150A, 480V, 3PH, MCC025-410. BUCKET (4E) 250A, 480V, 3PH, AND BUCKET (7B) 250A, 480V, 3PH. CONTRACTOR TO PROVIDE TEMPORARY CABLING AND DISTRIBUTION PANEL(S) AS REQUIRED FOR CONSTRUCTION NEEDS.
 9. CONTRACTOR SHALL COORDINATE WITH THE OWNER TO DETERMINE FINAL LOCATION OF SHORE POWER REEL AND ASSOCIATED DUCTBANK AND CONDUIT CONNECTIONS.
 10. DUCTBANK SECTION 1 TO BE INSTALLED UNDER SECTION 3.

- GENERAL NOTES:**
1. CONSTRUCTION AND DEMOLITION PHASING AND REQUIREMENTS FOR MAINTAINING PLANT OPERATIONS (MOP) ARE LISTED IN SECTION 01 52 00. CONTRACTOR SHALL CONDUCT DEMOLITION AND CONSTRUCTION IN ACCORDANCE WITH THE CONSTRAINTS LISTED IN SECTION 01 52 00-1.02.
 2. CONTRACTOR IS RESPONSIBLE FOR FIELD VERIFICATION OF EXISTING CONDITIONS IN ACCORDANCE WITH SECTION 01 52 00-1.05-B PRIOR TO CONSTRUCTION.
 3. CONTRACTOR SHALL SCHEDULE ALL OUTAGES REQUIRED TO COMPLETE THE WORK WITH THE OWNER FOR APPROVAL AND SCHEDULING, A MINIMUM OF TWO WEEKS IN ADVANCE. IN ACCORDANCE WITH SECTION 01 52 00-1.04-A.
 4. AFTER INSTALLATION OF ALL NEW MANHOLES AND DUCTBANK SECTIONS, INSTALL THE NEW 13.8KV AND CONTROL CIRCUITS IN ACCORDANCE WITH 01 52 00-1.14.
 5. IF NEW DUCTBANK CONNECTIONS TO THE EXISTING MANHOLES, AS SHOWN, CONFLICT WITH EXISTING DUCTBANKS, CONTRACTOR SHALL ADJUST ENTRY INTO THE MANHOLE BASED ON EXISTING CONDITIONS TO AVOID INTERFERENCE.
 6. MANHOLES AND HANDHOLES ARE SHOWN TO SCALE. SEE DETAILS FOR ADDITIONAL REQUIREMENTS.

Designed by: P. STRAKER	REV No. 0	DATE 5/16/25	REVISION DESCRIPTION ISSUED FOR BID	APPV RF		Signer Name: Ralph Frye Signing Reason: I approved this document. Signing Time: 2025-06-11 13:48:40(EDT)			ARLETTA SCOTT WILLIAMS EXECUTIVE DIRECTOR, ALCOSAN 3300 PREBLE AVE. PITTSBURGH, PA 15233 (412) 766 - 4810 www.alcosan.org	ALLEGHENY COUNTY SANITARY AUTHORITY WASTEWATER TREATMENT PLANT WET WEATHER PUMP STATION 000-ESP-04 ELECTRICAL SITE PLAN	Contract: 1800
Drawn by: P. STRAKER	1	6/12/25	ADD. 2 MANHOLE/HANDHOLE SIZING	RF							CAD File Name: 000-ESP-04.dwg
Checked by: R. FRYE											Date: 5/16/2025 Sheet: 328 of 405



MOTOR FLOOR POWER PLAN




GENERAL NOTES:

1. ALL CONTRACTOR PROVIDED ELECTRICAL EQUIPMENT ON THIS LEVEL SHALL BE RATED NEMA-4X.
2. GROUND JUMPERS TO THE GROUND RINGS ON ALL MAG METERS IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATION.

KEYNOTES:

1. COORDINATE WITH ALCOSAN AND OTHER DISCIPLINES REGARDING FINAL LOCATIONS FOR ANTENNAS.
2. WET WEATHER PUMPS PWW002-430, PWW003-430, PWW004-430, PWW005-430, AND PWW006-430 TYPICAL OF PWW001-430 WITH INSTRUMENTS TE, ZSH, SE, VE, PIT, FE, AND FIT.
3. FOR MOTOR WINDING LOOP NUMBERS (*) REFER TO SECTION 40 61 97 INSTRUMENT LIST.
4. CONNECT POWER TERMINATION BOXES TO GROUND RING WITH #2/0 AWG WIRE.
5. CONNECT CONTROL AND FLOAT SENSOR TERMINATION BOXES TO GROUND RING WITH #14 AWG WIRE.
6. CONNECT TO DISCHARGE PIPING FLOOR GROUND BUS WITH 4/0 BARE COPPER GROUND CONDUCTOR.
7. DISCONNECTS PROVIDED BY OTHERS. CONTRACTOR SHALL INSTALL DISCONNECTS.
8. TERMINATION BOXES PROVIDED BY OTHERS. CONTRACTOR SHALL INSTALL TERMINATION BOXES.





Plot Date: 6/10/2025 12:45:57 PM Path: BIM 360 // 170064 - ALCOSAN Wet Weather PS/170064-E-430V21.rvt

Designed by:	REVISION			
	REV No.	DATE	DESCRIPTION	APPV
P. STRAKER	0	5/16/25	ISSUED FOR BID	RF
Drawn by:	1	6/12/25	ADD. 2 ROTATE MOTOR ENCLOSURE	RF
P. STRAKER				
Checked by:				
R. FRYE				



Signer Name: Ralph Frye
Signing Reason: I approved this document.
Signing Time: 2025-06-11 13:48:40(EDT)



ARLETTA SCOTT WILLIAMS
EXECUTIVE DIRECTOR, ALCOSAN


3300 PREBLE AVE.
PITTSBURGH, PA 15233
(412) 766 - 4810

www.alcosan.org


ALLEGHENY COUNTY SANITARY AUTHORITY
WASTEWATER TREATMENT PLANT
WET WEATHER PUMP STATION

430-ET-03
MOTOR FLOOR POWER PLAN

Contract:	1800
CAD File Name:	
Date:	5/16/2025
Sheet:	359 of 413



PLAN




SECTION

1 TYPICAL MANHOLE (WITH GROUNDING)

1 NTS

- NOTES:
- SEE SPECIFICATIONS FOR ADDITIONAL REQUIREMENTS.
 - SEE ELECTRICAL DUCTBANK PROFILES FOR REQUIRED HEIGHT.




SECTION

2 TYPICAL HANDHOLE

2 NTS

- NOTES:
- SEE SPECIFICATIONS FOR ADDITIONAL REQUIREMENTS.
 - SEE ELECTRICAL DUCTBANK PROFILES FOR REQUIRED HEIGHT.




NOTE:

COMPACTED GRAVEL, 3/4\"/>

- D = 3\"/>

3 TYPICAL DUCTBANK DETAILS

3 NTS




NOTE:

PROVIDE 6\"/>

- D = 3\"/>


4 TYPICAL DUCTBANK DETAILS

4 NTS



5 TYPICAL CABLE RACK

5 NTS



COVER SECTION



6 TYPICAL MANHOLE COVER

6 NTS

Designed by:	REVISION			
P.STRAKER	REV No.	DATE	DESCRIPTION	APPV
Drawn by:	0	5/16/25	ISSUED FOR BID	RF
P.STRAKER	1	6/12/25	ADD. 2 MANHOLE/HANDHOLE SIZING	RF
Checked by:				
R.FRYE				



Signer Name: Ralph Frye
 Signing Reason: I approved this document.
 Signing Time: 2025-06-11 13:48:40(EDT)



ARLETTA SCOTT WILLIAMS
 EXECUTIVE DIRECTOR, ALCOSAN

3300 PREBLE AVE.
 PITTSBURGH, PA 15233
 (412) 766 - 4810

www.alcosan.org

ALLEGHENY COUNTY SANITARY AUTHORITY
 WASTEWATER TREATMENT PLANT
 WET WEATHER PUMP STATION

430-ED-03
 PROJECT DETAILS 1

Contract: 1800
 CAD File Name: 430-ED-03.dwg
 Date: 5/16/2025
 Sheet: 363 of 405